EXECUTIVE SUMMARY

1.1 Introduction

M/s. G.B. Overseas Pvt. Ltd. has an existing formaldehyde manufacturing unit at V.P.O. Rohad, District- Jhajjar, Haryana.

The plant was setup with the consent to establish dated 03.09.2009 from the Haryana State Pollution Control Board (HSPCB). Subsequently, the unit has started operation after obtaining consent to operate vide application no. HSPCB/BDR/Air Consent/6162 dated 28.12.2012.

The said project/activity is covered under category "**A**" (located outside Notified Industrial Area) of item **5(f)** "**Synthetic Organic Chemicals**" of the Schedule to the EIA Notification, 2006, and requires prior EC from Expert Appraisal Committee, MoEF&CC.

1.4 D	1.2 Basic Details of the Project						
S.No.	Particulars	Details					
1.	Nature and size of the Project	Capacity Expansion of Formaldehyde Manufacturing Unit in Existing Facility from 80 TPD to 250 TPD at V.P.O. Rohad, Distt. Jhajjar, Haryana by M/s G.B. Overseas Pvt.					
		Ltd.					
	Location details						
2.	Village /Town/Plot No.	Rohad					
	District	Jhajjar					
	State	Haryana					
	Area Details						
3.	Total Project Area	Total area available is 0.629 Hectare. No additional land is required for proposed expansion. Green belt will be developed in an area of 0.2185 Hectare (Approximately 34.75% of total land area).					
	Cost Details						
4.	Project Cost	Existing	Estimated cost proposed expan	-	Total		
4.		Rs. 1.32 Crores	Rs. 2.68 Crore	es	Rs. 4.00 C1	ores	
	EMP Budget	Rs. 0.20 Crores					
	Cost of OH&S	Rs. 0.03 Crores					
5.	Basic Requirements of the Project						
	Eroch Water (m2/day)	Existing	For Expansion		Total		
	Fresh Water (m3/day)	96 KLD	204 KLD	30	00 KLD		

1.2 Basic Details of the Project

CAPACITY EXPANSION OF FORMALDEHYDE MANUFACTURING UNIT IN EXISTING FACILITY FROM 80 TPD TO 250 TPD AT V.P.O. ROHAD, DISTT. JHAJJAR, HARYANA BY M/S G.B. OVERSEAS PVT. LTD.

	Source: HWRA					
	Existing	For Expansion	Total			
	489 KW	111 KW	600 KW			
Power	Source: UHBVN (Uttar Haryana Bijli Vitran Nigam)					
	DG sets as backup: 220 KVA (existing) 500 KVA (proposed)					
	Existing	Proposed expansion	Total	Fuel		
Boiler	1 boiler of 600 Kg/Hr Capacity	-	1 boiler of 600 Kg/Hr Capacity	HSD Fired		
Fuel	HSD					
Mannaytor	Existing	For Expansion	Total			
Manpower	10	15	25			

1.3 Production Capacity

Product	Existing Capacity	Proposed Expansion Capacity	Total Capacity after expansion
Formaldehyde	80 TPD	170 TPD	250 TPD

1.4 Raw Material Detail

The major raw material is Methanol which comes in road through tankers from Kandla Port, Gujarat & stored in underground M.S tanks. Methanol requirement for the existing unit is 40 TPD and after expansion, total 125 TPD will be required.

Raw	Existing	Proposed	Total
Material	Requirement	Requirement	Requirement
Methanol	40 TPD	85 TPD	

1.5 Project Benefits

- The setting up of the proposed plant will help in providing employment in priority to local people.
- There will be an increase in indirect employment and earnings of the small time shop owners like tea vendors, transporters, etc.

- The Project proponent has planned to contribute in socio-economic development of the area and will organize Blood donation camps, Education Programs, Health camps, Health awareness programs etc. and will continue to do so.
- The easy availability of infrastructure, manpower, raw materials will reduce the production cost as well as demand supply gap.
- The development of greenbelt in and around the plant premises will improve on the aesthetics of the area. Moreover, it will help in reducing the noise levels within the plant boundary.

1.6 Mitigation Measures for Control of Pollution

1.6.1 Air Pollution Control Measures

- Online Stack Monitoring System as an air pollution control measures to control the emission of particulate matter, the flue gas emission will remain well within gaseous emission norms prescribed by the CPCB.
- Scrubber will be installed for scrubbing the residual Formaldehyde from the main product stream which also controls the odour problem.
- To control the air emissions from D.G. Set, stack height of 6.0 m shall be provided.
- Green belt will be developed on 34.75% area of the total project area which will help in attenuating the pollutants emitted by the plant.
- Adequate measures for control of fugitive dust emissions will be taken.

1.6.2 Waste Water Treatment

There will be no waste water discharge from the plant. Zero Liquid Discharge (ZLD) concepts to be adopted. Domestic waste water after treatment (in septic tank) will be fully utilized with the facility for cleaning, flushing, water sprinkling and other non portable domestic purpose.

1.6.3 Noise Pollution Control

- Vibrating pads & acoustic enclosure will be provided to noise generating equipment to control noise level within norms.
- Latest technology and utmost care will be taken at the time of equipment/machinery installation.
- Lubrication of moving/rotating part or component of machineries will be done on regular basis.
- The operators working in the high-noise areas will be provided with ear-muffs or plugs.

- Acoustic enclosures and silencers will be provided to the equipment wherever necessary
- Proper green belt will be developed to reduce the noise level.
- Thus, it is envisaged that there will not be any adverse impacts of noise. The greenbelt developed within the premises will have significant beneficial impacts on reduction of noise within the periphery and outside the boundary.

1.6.4 Land Pollution Control

- The plant will implement zero level discharge concepts. The treated water will be recycled in the process. Therefore, there will not be any negative impact on soil.
- No toxic / waste water will be disposed directly on land.
- Other hazardous solid wastes will be sent to authorized recycler or vender.
- It is envisaged that there will not be any major impacts on land environment during the operation phase as most of the effluent generated shall be reused in the process.

1.6.5 Solid & Hazardous Waste Generation and Disposal

- Used Oil generated will be sold to authorised recycler.
- Solid waste from evaporator will be sent to TSDF.

All the Solid & hazardous waste generated, will be collected, stored separately and disposed off as per the guidelines issued by CPCB & Haryana State Pollution Control Board.

1.7 Environmental Management Plan (EMP)

The total capital investment on environmental control measures is envisaged to be about **Rs 0.20 Crores** out of a total expansion project cost of **Rs 4.0 Crores**. Details are given in below table:

S. No.	Particulars	Initial Cost (in Lakhs)	Recurring Cost (per year)
1.	Air Pollution Control- Wet Scrubber	4.00	0.5
2.	Stack with online Monitoring System	5.00	0.5
3.	Single Stage Evaporator	4.50	0.4
4.	Ocuupational Health and safety	3.00	0.2
5.	Green Belt Development	2.00	0.4

CAPACITY EXPANSION OF FORMALDEHYDE MANUFACTURING UNIT IN EXISTING FACILITY FROM 80 TPD TO 250 TPD AT V.P.O. ROHAD, DISTT. JHAJJAR, HARYANA BY M/S G.B. OVERSEAS PVT. LTD.

6.	Rain Water Harvesting Pit	1.50	0.3
	Total	20.0 Lakh (0.20 Crores)	2.3 Lakh (0.023 Crores)

1.8 National Parks or Wild Life Sanctuary

There is no Wild Life Sanctuary or National Park within 10 km radius of the Project Site hence no NBWL Clearance required. No forest land involved within the project site.

1.9 Demography & Socio-Economic Environment

- Improvement of infrastructure, transportation, health care and education facility.
- Direct and indirect employment will be generated like business, contract works and development work like roads, etc. and other welfare amenities such as medical facilities, conveyance, free education, drinking water supply etc.
- The impact of employment opportunities will not be significant due to low level of education and skills in the area which will result in sourcing skilled work force from outside the immediate area.
- Skill based training to local employed people will be given by project proponent.
- The interaction and intermingling of all these people will improve the understanding of various cultures and will definitely improve and strengthen friendliness, brotherhood and unity among them.